



PARTS LIST			
ITEM	QTY	PART NUMBER	DESCRIPTION
1	180.000 in	ASTM A 53/A 53M Pipe 12 - Schedule 40 - 180	Tower Support Structure
2	1	ASME B16.5 Flange Welding Neck - Class 150 12	Pipe Flanges - Flange Welding Neck - Class 150.Inch
3	1	ASME B16.5 Flange Welding Neck - Class 150 6	Pipe Flanges - Flange Welding Neck - Class 150.Inch
4	1	ASME B16.9 Long Radius 90 Deg Elbow 6 x 0.28	Wrought Butt welding Fitting - Long radius 90 Deg Elbow.Inch
5	148.000 in	ASTM A 53/A 53M Pipe 6 - Schedule 40 - 148	Monitor Riser Pipe
6	1	6x4conc	Transition Fitting
7	1	ASME B16.5 Flange Welding Neck - Class 150 4	Pipe Flanges - Flange Welding Neck - Class 150.Inch
8	1	deluge	Bermad Monitor ON/OFF Valve 24 VDC
9	1	om1500	Oscillating Monitor
10	170.000 in	ANSI/ASME B36.19M Pipe 4 - Schedule 5S - 170	Water Motor Discharge Pipe
11	160.000 in	ASME B36 1/2" Rod	Oscillating Water Powered Motor ON/OFF Lever/Shaft
12	1	grip	
13	1	ANSI/AFBMA 15 - 1 x 1.5 x 0.53	Eccentric Locking Collar

DRAWN DA	02/15/2002	FLAMEOUT DESIGN & FABRICATION HOUSTON, TEXAS	
CHECKED DG	02/15/2002	TITLE	
QA		DISTRAGAS OSCILLATING MONITOR TOWER	
MFG MM	02/15/2002	SIZE D	DWG NO 2002-DG-00001
APPROVED BC	02/15/2002	SCALE	REV 2
		SHEET 1 OF 1	